

Construction Manual

Construction Manual

This document is a guide for volunteers to assist Habitat for Humanity Central Arizona build and renovate simple, decent, affordable homes. It is a detailed, task-based list of the activities that need to be done to complete a Habitat house. General activity descriptions and related illustrations, where appropriate, are included.

It is expected that the House Leader will hold a Morning Briefing to review safety issues, introduce the homeowner(s) and describe the day's work for each new group of volunteers. See the Typical Work- day outline for the specific items to be covered each week. Always consider that most volunteers are not acclimated to the work and weather conditions they will experience. It is also important to emphasize the need for a clean and orderly site during the workday as well as at the end of the day. Utilize the volunteers as much as possible to clean the site and when applicable, to empty trash barrels into dumpsters.

The old expression says that there are many ways to skin a cat. It certainly applies to building a house. This document is a work in progress. The methods that you will find in this manual are not the only way to do things. What they are is a compilation of what has worked best and been easiest for our volunteers over the last 15 plus years. Please try these techniques (and master them) before doing things a different way. Consistently following these directions makes building houses easier for everyone.

Once you are proficient at the methods in the manual, do not be hesitant to seek out the "best practices" of others. Visiting the crews at other Habitat Houses, attending our training sessions and searching the internet are all good ways to learn.

If you have found a better way for you, please share it with us on staff. It may truly be a better way for everyone, and since we try to do everything that we can to make your jobs as easy as possible, we will add it to the next edition of the manual. Even if it turns out to be a better way only for you, we still would like to know about it.

When it comes to making things easier for our general volunteers, there is nothing that you can do that will do more for them than for you to read the applicable section of your manual each time before you go on site. Also, please bring the manual with you every time you come out, it is a great reference source.

If there is anything in this manual that you would like to know more about, please talk to your site supervisor. If after that you still have questions or would like to make suggestions (and they are welcome) to improve the manual in the future, please feel free to call or e-mail the field operations manager or the assistant director of construction. We would like to thank the volunteers and professionals who helped with this manual.

Thank you for all that you give of yourselves. Your dedication and participation are greatly appreciated.

This Manual belongs to:

Contact Number:

Revised: August 2021.

Table of Contents

PRE-BUILD	1
Overview	4
Container Shelves & Rack	5
Container Maintenance	6
Cut Table	6
Post-Tensioned Slab	7
Slab Layout	8
Marking the Slab	11
Shear Panels	12
Cutting Plates	13
Marking Plates	14
Cut Lists	16
Building Modules	19
FRAMING	22
Framing Walls	26
Framing Doors	27
Framing Windows	30
Balloon Framing	31
Raising Walls	31
Anchoring Wall Plate	33
Racking Exterior Walls	34
Straightening Walls	34
Pony Wall	36
Backing Electrical Panel	37
Beams, Pockets, Posts	37
Beam Pocket Construction	37
Post Construction	38
Beam Installation	39
Flat Roofs	39
Truss Layout	39
Parapet Walls	40
Sheathing	42
Window & Door Holes	43
Special Shear Panels	44
Fall Protection	44
Scaffolding	44
Assembly	44
Second Story Framing	47

Floor Trusses & Deck.....	48
Second Story Walls.....	48
Stairway Construction.....	49
Air Sealing.....	51
Tub Blocking.....	52
ROOF FRAMING	53
Truss Layout.....	56
Wall Walker Installation.....	56
Gable Modules.....	57
Installing Trusses.....	64
Frieze Boards.....	65
Hurricane Clips.....	66
OSB Stacker.....	66
Drywall Blocking.....	67
Outriggers.....	68
Cutting Truss Tails.....	69
Fascia & Shingle Molding.....	70
Roof Guards.....	70
Safety Rail Set-Up.....	71
Proper Installation of Extension Ladder.....	72
Roof Decking.....	77
Knee Braces & Gable Ties.....	79
Shear Wall/Truss Connections.....	80
Valley Trusses.....	80
Attic Access.....	81
Attic Air Handler Platform.....	82
Stucco Stop.....	83
Enclosing an Actual Beam.....	83
False Box Beam.....	84
Plumb & Anchor Interior Walls.....	84
Truss Clips.....	85
Strap & Shear Inspection Checklist.....	87
ROOFING	87
Roof Preparation.....	90
Underlayment.....	91
Attic Vents.....	92
Shingling.....	93
Roof Valleys.....	95
Ridge Cap.....	96
DRYWALL PREPARATION	97
Water Heater Platform.....	100

Blocking	100
Closet Air Handler Platform	101
Interior Framing	102
Square Walls	103
Marking Locations	103
Sealing the Air Envelope	103
Pre-Drywall Inspection Checklist	104
DRYWALL	105
Hanging Drywall	108
General Instructions	113
Scuttle Hole	114
Water Heater Loop	114
Final Details	114
TRIM	115
Hinged Doors	118
Exterior	118
Interior	119
Closet Doors	120
Cleating	122
Closet Shelving	122
Sealing Air Gaps	123
Baseboards	123
Scuttle Hole	124
Stairs	124
Caulk & Spackle	125
PAINT	127
Painting	130
Interior Painting	130
Exterior Painting	132
Painting Doors	132
LANDSCAPE	134
Landscaping	136
DETAILS & FINAL CLEAN-UP	138
Cabinets	141
Countertops	142
Security Door	143
Bathroom Accessories	144
Door Hardware	145
Final Punch List & Clean Up	145
Mailbox	146

MASONRY	148
Masonry Walls at Property Line and Returns	149
DEMOLITION & RENOVATION	154
Sequence of Renovation	157
Bearing Walls.....	157
Roofing Removal	158
Roof Sheathing Removal.....	160
Roof Framing Repair.....	160
Stucco Removal	160
Window Removal	160
Drywall Removal	161
Systems Demolition	161
Wall Framing Demolition	161
Other Demolition Activities	161
Framing Bi-Fold Doors.....	162
Installing Bi-Fold Doors	162
Installing Redheads	162
Enclosing A Post.....	163
Interior Soffit	164
CONSTRUCTION VOCABULARY	165